

Carolina Place Gravity Sewer Rehabilitation Project

The Carolina Place Gravity Sewer Rehabilitation Project will focus on rehabilitating gravity sanitary sewer in alley ways (see below map). The alley ways were chosen due to the difficulty to access the sewer mains with equipment when issues arise. The rehabilitation process begins with cleaning and televising the sewer mains. Any defects found within the sewer main are noted on televising reports. Defects can include cracked or broken pipe, holes, offset joints, etc. The reports will determine the method of rehabilitation with excavated point repair and/or lining the sewer main.

As of March 26th, 2020, all the sewer mains have been cleaned and televised in the project area. The televising data has been sent to WK Dickson to be reviewed and to determine any necessary repairs that need to take place before the rehabilitation process can begin.

This project is anticipated to be completed in September of 2020.

